

ADDENDUM NO. 3

June 20, 2023

RE: **HVAC Unit Replacement
Clarksville Middle School
6535 South Trotter Road
Clarksville, MD 21029
(HCPSS Bid #130.23.B3)**

FROM: **Purchasing Office
Howard County Public Schools
10910 Clarksville Pike
Ellicott City, MD 21042
(410) 313-6723
(410) 313-6789 fax**

TO: **APPROVED PROSPECTIVE BIDDERS**

This addendum forms a part of the Contract Documents and modifies the Original Bidding Documents as noted below. Acknowledge receipt of this Addendum in the space provided on the Form of Proposal. Failure to do so may subject the Bidder to disqualification. This Addendum consists of 1 page.

QUESTIONS:

1. Per electrical drawing we are to reuse the existing 3/4 conduit for the new HPU's. Per the panel schedule the new units require 2-#3 & 1-#8 conductor. The existing 3/4 conduit is too small for the new conductors. Can you please let us know how to proceed?

Response: Furnish and install 1" EMT conduit and flex metal conduit for branch circuit wiring for all (7) new HPUs. Conceal above ceiling and within the exterior wall. Seal conduit wall penetrations. Remove existing conduits back to designated source panels.

CHANGES TO THE DRAWINGS:

None

CHANGES TO THE SPECIFICATIONS:

None

END OF ADDENDUM NO. 3